


PROPOSED SITE PLAN - 43 MATTAKEESETT STREET CENTER PROTECTION & RESIDENTIAL A DISTRICT DEVELOPMENT

(ASSESSOR'S PARCEL C9-17)

PEMBROKE, MASSACHUSETTS





THIS SITE PLAN APPROVAL DOES NOT NECESSARILY INDICATE COMPLIANCE WITH THE PEMBROKE ZONING BY-LAW

DATE OF ENDORSEMENT:


DEMODORE DI ANNINO DOAG


<u>OWNER</u>

OLD SALT REALTY TRUST 387 MAIN STREET PLYMPTON, MA 02367

<u>APPLICANT</u>

JEFFREY PERETTE
387 MAIN STREET
PLYMPTON, MA 02367





ABBREVIATIONS

APPROX APPROXIMATE
CNTY BND COUNTY BOUND
CCB CAPE COD BERM

CIP CAST IN PLACE CONCRETE CURB

CONCRETE CONCRETE
DMH DRAINAGE MANHOLE
E ELECTRIC
FND. FOUND

ELEV ELEVATION
EXIST EXISTING
FES FLARED END SECTION

GAS

I INVERT

MAX MAXIMUM

MIN MINIMUM

NTS NOT TO SCALE

OHW OVERHEAD WIRE

PROP PROPOSED

PVC POLYVINYLCHLORIDE PIPE
RCP REINFORCED CONCRETE PIPE
S SEWER
SB/DH STONE BOUND/DRILL HOLE

TYP TYPICAL
UP UTILITY POLE
W WATER

<u>LEGEND</u>

EXISTING	PROPOSED		
55	100	CONTOUR ELEVATION	
		EROSION CONTROL / LIMIT OF WORK	
x100.2	+100.00	SPOT GRADE	
0	D	DRAIN MANHOLE (DMH)	
III		CATCH BASIN (CB)	
		ROOF DRYWELLS	
\(\rightarrow \)	¢	UTILITY POLE (UP)	
		DECIDIOUS TREE	
		LIGHT	
- 0-	•	SIGN	
فر	گ	VAN-ACCESSIBLE HANDICAP PARKING	
		FENCE	
		HANDICAP RAMP	
~~~~	~~~~	TREE LINE	

## RESIDENTIAL A DISTRICT ZONING REQUIREMENTS

MIN. LOT SIZE 40,000 S.F (80% UPLAND)

MIN. LOT FRONTAGE 150 L.F.

FRONT YARD SETBACK 40 FT

FRONT YARD SETBACK 40 FT.

REAR YARD SETBACK 25 FT.

SIDE YARD SETBACK 20 FT.

MAX BUILDING HEIGHT 2.5 STORIES

# CENTER PROTECTION DISTRICT ZONING REQUIREMENTS

MIN. LOT SIZE 40,000 S.F

MIN. LOT FRONTAGE 150 L.F.

FRONT YARD SETBACK 40 FT.

REAR YARD SETBACK 20 FT.

SIDE YARD SETBACK 20 FT.

MAX BUILDING HEIGHT 2.5 STORIES OR 36'

# GENERAL NOTES

1. LOCUS OWNER: ASSESSOR'S MAP C9, PARCEL 17

OLD SALT REALTY TRUST

387 MAIN STREET

PLYMPTON, MASSACHUSETTS 02367

- 2. DEED BOOK REFERENCE: PLYMOUTH COUNTY REGISTRY OF DEEDS DEED BOOK 20047, PAGE 89
- 3. LOCUS IS SHOWN AS ASSESSOR'S MAP C9, PARCEL 17
  TOWN OF PEMBROKE ASSESSOR'S MAPS. TOTAL AREA = 2.53± ACRES
- 4. LOCUS IS LOCATED IN RESIDENTIAL A AND CENTER PROTECTION DISTRICTS
- 5. LOCUS FALLS WITHIN ZONE "X" AS SHOWN ON THE FIRM COMMUNITY PANEL NO: 25023C 0204J DATED JULY 17, 2012. ZONE "X" IS NOT A SPECIAL FLOOD HAZARD AREA.
- 6. ALL EXISTING CONDITIONS & TOPOGRAPHIC INFORMATION WAS OBTAINED FROM AN ON-SITE SURVEY CONDUCTED BY GRADY CONSULTING, L.L.C. IN APRIL 2015.
- 7. ALL LOCATIONS OF SUBSURFACE UTILITIES AND STRUCTURES WERE OBTAINED FROM AVAILABLE TOWN AND UTILITY RECORDS. THE SIZE, TYPE AND LOCATION OF UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL PROPERLY LOCATE THE UTILITIES PRIOR TO THE BEGINNING OF CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN UTILITY INFORMATION BY CONTACTING DIGSAFE (888–344–7233). THE CONTRACTOR SHALL EXCAVATE TEST PITS TO VERIFY UTILITY LINE LOCATIONS AS NECESSARY.
- 8. ANY CHANGE IN THE FIELD CONDITIONS SHOULD BE REPORTED TO THE ENGINEER TO INSURE THAT ANY MODIFICATIONS TO THE ORIGINAL DESIGN ARE PROPER AND ADEQUATE TO SERVE THE PROJECT'S NEEDS, AND COMPLY WITH THE APPLICABLE STANDARDS AND REGULATION.
- 9. NO WETLAND RESOURCE AREAS WERE OBSERVED ON—SITE BY MORSE ENGINEERING COMPANY, INC. DURING JULY 2019.
- 11. EXISTING BUILDING AND SEPTIC SYSTEM LOCATIONS SHOWN ON ABUTTING PROPERTIES WERE COMPILED FROM AVAILABLE DATA ON RECORD AT THE PEMBROKE BOARD OF HEALTH.

### GENERAL UTILITY NOTES

- 1. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY, AND "DIGSAFE" AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION WORK TO REQUEST EXACT FIELD LOCATION OF UTILITIES AND THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES INTERFERING WITH THE PROPOSED CONSTRUCTION AND APPROPRIATE REMEDIAL ACTION TAKEN BEFORE PROCEEDING WITH THE WORK. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLAN.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING AND MAINTAINING ALL CONTROL POINTS AND BENCHMARKS NECESSARY FOR THE WORK.
- 3. SEE PLANS 6 FOR CONSTRUCTION DETAILS, NOTES, AND SPECIFICATIONS.
- THE CONTRACTOR SHALL PROVIDE INLET PROTECTION, SUCH AS SILT SOCKS, AT ALL
  4. CATCH BASINS TO PREVENT SEDIMENT FROM ENTERING THE INFILTRATION / DETENTION BASIN.
- 1. LOCUS OWNER: <u>ASSESSOR'S MAP C9, PARCEL 17</u>
  OLD SALT REALTY TRUST
  387 MAIN STREET
- 2. DEED BOOK REFERENCE: PLYMOUTH COUNTY REGISTRY OF DEEDS
  DEED BOOK 50545, PAGE 196

PLYMPTON, MASSACHUSETTS 02367

# **DEED REFERENCE:**

PLYMOUTH COUNTY REGISTRY OF DEEDS BOOK 50545, PAGE 196 RECORD OWNER: OLD SALT REALTY TRUST

# PLAN REFERENCES:

- 1. PLAN BOOK 9 PAGE 435 2. PLAN BOOK 7 PAGE 43
- 3. PLAN BOOK 7 PAGE 43
- 4. PLAN BOOK 13 PAGE 873 5. COUNTY LAYOUT DECREE NO. 942

WITH THE PEMBROKE ZONING BY—LAW
DATE OF ENDORSEMENT:


THIS SITE PLAN APPROVAL DOES NOT NECESSARILY INDICATE COMPLIANCE

PEMBROKE PLANNING BOARD

TOWN OF PEMBROKE, MA HEREBY CERTIFY THAT THE NOTICE OF APPROVAL OF THIS PLAN BY THE PLANNING BOARD HAS BEEN RECEIVED AND RECORDED AT THIS OFFICE AND NO APPEAL WAS RECEIVED DURING THE NEXT TWENTY DAYS AFTER RECEIPT AND RECORDING OF SAID NOTICE

TOWN CLERK OF THE







# **DIMENSIONAL REGULATIONS**


ZONING / DIMENSIONAL REQUIREMENTS


RESIDENTIAL A DISTRICT

COMPONENT	REQUIRED	EXISTING
MINIMUM LOT AREA	40,000 S.F. (80% UPLAND)	110,230± S.F. (2.53 ACRES) (100% UPLAND)
FRONTAGE	150'	154.5'
FRONT YARD SETBACK	40'	226.8'
SIDE YARD SETBACK	20'	21.6'
REAR YARD SETBACK	25'	150.1'
BUILDING HEIGHT	2.5 STORIES (MAX)	_


### CENTER PROTECTION DISTRICT


COMPONENT	REQUIRED	EXISTING
MINIMUM LOT AREA	40,000 S.F.	110,230± S.F. (2.53 ACRES) (100% UPLAND)
FRONTAGE	150'	154.5'
FRONT YARD SETBACK	40'	226.8'
SIDE YARD SETBACK	20'	21.6'
REAR YARD SETBACK	20'	150.1'
BUILDING FLOOR AREA	15% (MAX) OR 9,000 S.F. (MAX)	7.3%
IMPERVIOUS LOT COVERAGE	65% (MAX)	13.2%
LANDSCAPING	35% (MIN)	35%
BUILDING HEIGHT	2.5 STORIES (MAX) OR 36' (MAX)	-







# MULCH SOCK DETAIL SCALE: NOT TO SCALE





NOT TO SCALE





1) ALL ROOF LEADERS SHALL BE EQUIPPED WITH DOWNSPOUT STRAINERS.

2) NO CONSTRUCTION ACTIVITY (TRAFFIC) SHALL BE ALLOWED OVER THE LEACHING DRY WELL AREAS.


3) NO CONSTRUCTION SURFACE WATER OR DEWATERING DISCHARGES SHALL BE DISCHARGED INTO

THE DRYWELL STRUCTURES OR DRYWELL SITE LOCATIONS.

4) DRYWELLS SHALL BE LOCATED A MINIMUM OF 10' FROM FOUNDATIONS & 10' FROM PROPERTY

SUBSURFACE LEACHING DRYWELL

NOT TO SCALE



PEMBROKE PLANNING BOARD

I, _______ TOWN CLERK OF THE TOWN OF PEMBROKE, MA HEREBY CERTIFY THAT THE NOTICE OF APPROVAL OF THIS PLAN BY THE PLANNING BOARD HAS BEEN RECEIVED AND RECORDED AT THIS OFFICE AND NO APPEAL WAS RECEIVED DURING THE NEXT TWENTY DAYS AFTER RECEIPT AND RECORDING OF SAID NOTICE

