
SITE DEVELOPMENT PLANS FOR HERRING BROOK SOLAR PROJECT


OCATED AT

0 HOBOMOCK STREET
PEMBROKE, MASSACHUSETTS
DATE: MAY 31, 2019
REVISED: AUGUST 12, 2019





VICINITY MAP

1" = 800'



 $\frac{LOCUS\ MAP}{1" = 800'}$





<u>OWNER:</u>

GEORGE R. GOULD JR P.O. BOX 686 BRYANTVILLE, MA 02327

APPLICANT:

CENTRICA BUSINESS SOLUTIONS
7484 CANDLEWOOD ROAD, SUITE T-W
HANOVER, MD 21076

ENGINEER:



P.O. Box 1051, Sandwich, MA 02563
PHONE NUMBER: (508) 888-9282

THIS SITE PLAN APPROVAL DOES NOT
NECESSARILY INDICATE COMPLIANCE
WITH THE PEMBROKE ZONING BY-LAW

DATE		
		_
		
		_
		_
		_
		_

SUMMARY OF REQUESTED WAIVERS

SECTION IV — SIITE PLAN CONTENT

4.7 LANDSCAPE PLAN
4.10 BUILDING ELEVATIONS

PEMBROKE PLANNING BOARD


4.21 PHOTOMETRIC PLAN

4.22 TRAFFIC IMPACT STUDY

I, TOWN CLERK OF THE TOWN OF PEMBROKE, MA HEREBY CERTIFY THAT THE NOTICE OF APPROVAL OF THIS PLAN BY THE PLANNING BOARD HAS BEEN RECEIVED AND RECORDED AT THIS OFFICE AND NO APPEAL WAS RECEIVED DURING THE NEXT TWENTY DAYS AFTER RECEIPT AND RECORDING OF SAID NOTICE.


DATE








OVERALL LOCATION PLAN


SCALE: 1" = 200'














4" CEMENT CONCRETE SIDEWALK

—GRAVEL BASE M 1.03 TYPE I

CEMENT CONCRETE

(TYPE

LIMITS OF CEMENT CONCRETE

DEPTH OF LEFT SIDE CURB LEVEL LANDING TRANSITION LENGTH

(SEE TABLE)

-

RAMP

DETECTABLE WARNING

— PANEL PLACEMENT

LEVEL LANDING >5. FT (TYP.)

RAMP REFERENCE POINT (TYP.

SIDEWALK

SIDEWALK/WHEEL

CHAIR RAMP

4000 PSI, 3/4", 610

(BROOM FINISH)

1.∵′ું છ

6" REVEAL -

BASE COURSE

GRAVEL SUBBASE

BROUGHT UP TO BOTTOM OF BASE COURSE.

LIMITS OF CEMENT CONCRETE

FOR DRAINAGE (TYP.)

RAMP REFERENCE POINT (TYP.) -

RIGHT SIDE CURB

(SEE TABLE)

SIDEWALK

REFERENCE MHD CONSTRUCTION STANDARD M/E 107.9.0

THIS PROCEDURE IS APPLICABLE ONLY IF CURB IS TO BE SET AFTER BASE AND/OR BINDER

COURSES ARE IN PLACE, OTHERWISE CEMENT CONCRETE WILL BE ELIMINATED AND GRAVEL IS


VERTICAL GRANITE CURB


(NOT TO SCALE)


CEMENT CONCRETE SIDEWALK/

WHEELCHAIR RAMP SECTION

(NOT TO SCALE)







LOCAL/NATIVE/ NON INVASIVE

SCRUB SHRUE

NOTE: PRIOR TO CONSTRUCTION, TEST PITS AT BASIN LOCATIONS ARE TO BE PERFORMED BY A LICENSED SOIL EVALUATOR TO DETERMINE ESTIMATED SEASONAL HIGH

FROM WHAT IS SHOWN ON THE PLANS, CONTRACTOR SHALL CONTACT DESIGN ENGINEER FOR POSSIBLE DESIGN MODIFICATION.

GROUNDWATER (ESHGW). IF THE ESHGW ELEVATION OBSERVED AT THE TIME OF THE TEST PITS DIFFERS

UN-COMPACTED APPROVED

ROOTS, LARGE ROCKS &

NATIVE SUBGRADE FREE OF

24" MIN. SOIL-

MIX DEPTH

REFER TO PLAN

FILTRATION

LOCAL/NATIVE/NON INVASIVE

HERBACEOUS

65.82

TYPICAL RAINGARDEN CROSS-SECTION (TYP)

NOT TO SCALE


воттом

10-YEAR

25-YEAR

100-YEAR

EVERY 2 L.F. WHEN NOT O PROTECTED AREA PLAN VIEW 1-1/8"x1-1/8" WOOD STAKE EVERY 2 L.F. WHEN NOT ON B" COMPOST-FILLED SILT SOCI DISTURBED AREA -TRAPPED SEDIME SECTION VIEW



SEDIMENT AND EROSION CONTROL NOTES:

- PRIOR TO COMMENCING SITE WORK OR EARTHWORK OPERATIONS, INSTALL
- SEDIMENT CONTROL BARRIERS AND MAINTAIN THROUGHOUT CONSTRUCTION. 2. ALL DISTURBED AREAS SHALL BE LOAMED AND SEEDED IMMEDIATELY UPON COMPLETION OF CONSTRUCTION.
- ALL MATERIALS AND STOCKPILES SHALL BE STORED ON LEVEL AREAS OUTSIDE OF ANY FLOOD ZONES, WETLANDS OR BUFFER ZONE AREAS. ALL STOCKPILES SHALL BE SURROUNDED BY SILT SOCK. SHALL HAVE SIDE SLOPES NO GREATER THAN 30% AND SHALL BE SEEDED OR STABILIZED IF LEFT UNDISTURBED FOR TWO WEEKS OR MORE.
- SEDIMENTATION CONTROL DEVICES AND EROSION CONTROL BARRIERS SHALL BE INSPECTED WEEKLY AND MAINTAINED AS NECESSARY THROUGHOUT ALL PHASES OF CONSTRUCTION AND PROMPTLY AFTER EACH
- 5. ANY SLOPE STEEPER THAN 3:1 SHALL BE EQUIPPED WITH SLOPE STABILIZATION FABRIC OR EROSION CONTROL MATTING.
- 6. ADDITIONAL SEDIMENT CONTROL MEASURES SHALL BE INSTITUTED AS CONDITIONS WARRANT OR AS DIRECTED BY THE ENGINEER AND/OR THE


EXISTING OR PROPOSED WATERCOURSES (BOTH TEMPORARY OR

- THE CONTRACTOR MUST REPAIR OR RE-SEED ANY AREAS THAT DO NOT DEVELOP WITHIN A PERIOD OF ONE YEAR AT NO ADDITIONAL EXPENSE TO
- 8. MATERIAL STOCKPILES SHALL NOT BE LOCATED WITHIN THE PATH OF
- PERMANENT) OR THOSE AREAS SUBJECT TO STORM WATER FLOW. SEDIMENT CONTROL DEVICES AND SEDIMENT CONTROL BARRIERS MAY BE
- REMOVED ONLY AFTER THE SITE HAS BEEN STABILIZED AND APPROVED BY 10. ALL DISTURBED OR EXPOSED AREAS SUBJECT TO EROSION, WHICH REMAIN DISTURBED BUT INACTIVE FOR AT LEAST 14 DAYS, SHALL RECEIVE TEMPORARY SEEDING IN ACCORDANCE WITH THE MASSACHUSETTS EROSION

AND SEDIMENT CONTROL GUIDELINES. IN ALL CASES, STABILIZATION

MEASURES SHALL BE IMPLEMENTED AS SOON AS POSSIBLE IN

- ACCORDANCE WITH THE MASSACHUSETTS EROSION AND SEDIMENT CONTROL GUIDELINES. 11. EARTHWORK ACTIVITY ON THE SITE SHALL BE DONE IN A MANNER SUCH THAT RUNOFF IS DIRECTED AWAY FROM ABUTTING STRUCTURES,
- 12. THE CONTRACTOR SHALL KEEP ON SITE AT ALL TIMES ADDITIONAL SILT SOCK AND EXTRA SILTATION FENCING FOR INSTALLATION AT THE DIRECTION OF THE ENGINEERS, CONSERVATION COMMISSION, OR THE BOARD TO MITIGATE ANY EMERGENCY CONTROL.
- 13. REFER TO CONSTRUCTION DETAILS FOR ADDITIONAL EROSION CONTROL
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SITING, RELOCATION AND AUGMENTATION OF SEDIMENT AND EROSION CONTROL DEVICES AS THE PROJECT PROGRESSES AND THE SITE DRAINAGE CONDITIONS CHANGE.
- 15. THE CONTRACTOR SHALL MINIMIZE THE AREA OF DISTURBED SOIL. EFFORTS SHALL BE MADE TO LIMIT THE TIME OF EXPOSURE OF DISTURBED
- 16. ANY DISTURBED SOILS NOT PERMANENTLY STABILIZED PRIOR TO OCTOBER 15 OF ANY YEAR SHALL BE TEMPORARILY STABILIZED TO PREVENT EROSION UNTIL ACTIVE USE RESUMES.
- 17. SEDIMENT CONTROLS SHALL NOT CONTAIN ANY NYLON MESH OR NETTING FOUND TO BE A HAZARD TO LOCAL WILDLIFE. HAYBALES SHALL NOT USED AS SEDIMENT CONTROL DUE TO THE POTENTIAL TO SPREAD INVASIVE PLANT SPECIES. 100% BIO-DEGRADABLE CONTROLS ARE PREFERRED, SUCH AS ROLLED EROSION CONTROL PRODUCTS 9I.E., MULCH CONTROL NETTING. EROSION CONTROL BLANKETS. TURF MATS. MULCH SOCKS, FIBER ROLLS, WATTLES, ETC.) WHICH MUST BE 100% NATURAL BIO-DEGRADABLE MATERIAL. PHOTO-DEGRADABLE, UV DEGRADABLE OF OXO-(BIO)DEGRADABLE PLASTICS ARE NOT CONSIDERED BIO-DEGRADABLE.



CONSTRUCTION PERIOD STORMWATER OPERATION AND MAINTENANCE:

INSPECT AFTER EVERY MAJOR STORM EVENT (2" OR GREATER) DURING CONSTRUCTION AND FOR THE FIRST FEW MONTHS AFTER CONSTRUCTION TO

FNSURF PROPER STABILIZATION AND FUNCTION, THEREAFTER INSPECT AT LEAST TWICE PER YEAR DURING WET WEATHER TO ENSURE THE

BIO-RETENTION/RAIN GARDENS ARE DRAINING PROPERLY AND VEGETATION IS

INSPECTION. REMOVE SEDIMENT AS NECESSARY DURING CONSTRUCTION, WHILE

THE CONSTRUCTION ENTRANCE TRACKING PADS SHOULD BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOW OF SEDIMENT ONTO THE

ADDITIONAL STONE. THE ENTRANCE PAD SHOULD BE INSPECTED WEEKLY AT

PERIODS OF HEAVY USE. WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS

PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH

A MINIMUM, AFTER MAJOR STORM EVENTS (2" OR GREATER) AND DURING

THE GRAVEL, THE PAD SHOULD BE TOP DRESSED WITH NEW STONE OR

YOUR SITE ONTO PAVED ROADS. SIDEWALKS. OR OTHER PAVED AREAS

REPLACED COMPLETELY. WHERE SEDIMENT HAS BEEN TRACKED-OUT FROM

OUTSIDE OF YOUR SITE. REMOVE THE DEPOSITED SEDIMENT BY THE END OF

OF THE NEXT BUSINESS DAY IF TRACK-OUT OCCURS ON A NON-BUSINESS DAY. REMOVE THE TRACK-OUT BY SWEEPING, SHOVELING, OR VACUUMING

INSPECT MONTHLY AT A MINIMUM, OR AFTER MAJOR STORM EVENTS (2"OR

MMEDIATELY AFTER INSPECTION. ACCUMULATED SEDIMENT SHALL BE REMOVED

WHICHEVER OCCURS FIRST. SEDIMENT SHALL BE DISPOSED OF IN A SUITABLE

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER AND EROSION CONTROL FACILITIES UNTIL

ALL COMPONENTS OF THE STORMWATER MANAGEMENT SYSTEM AT THE

COMPLETION OF CONSTRUCTION, IMMEDIATELY PRIOR TO TURNING OVER

2. UPON COMPLETION OF CONSTRUCTION, THE OPERATION AND MAINTENANCE OF

THE PROJECT CONSTRUCTION IS COMPLETED. THE CONTRACTOR SHALL CLEAR

OPERATION AND MAINTENANCE RESPONSIBILITY TO THE PROJECT PROPONENT.

ALL COMPONENTS OF THE STORMWATER MANAGEMENT SYSTEM WILL BE THE RESPONSIBILITY OF THE SYSTEM OWNER:

CENTRICA BUSINESS SOLUTIONS

THE SYSTEM OWNER SHALL COMPLY WITH THE POST CONSTRUCTION LONG TERM STORMWATER OPERATION AND MAINTENANCE PLAN APPROVED FOR THIS PROJECT.

THERE SHALL BE NO ILLICIT DISCHARGE OF ANY WASTE OR WASTE WATER

INTO THE STORMWATER MANAGEMENT SYSTEM. THE MAINTENANCE OF THE

FACILITY SHALL BE UNDERTAKEN IN SUCH A MANNER AS TO PREVENT AN'

DISCHARGE OF WASTE OR WASTE WATER INTO STORMWATER MANAGEMENT SYSTEM. ANY WASTE OIL OR OTHER WASTE PRODUCTS GENERATED DURING MAINTENANCE SHALL BE PROPERLY DISPOSED OF OFF SITE.

HANOVER, MD 21076

7484 CANDLEWOOD ROAD, SUITE T-W

GREATER) DURING AND AFTER CONSTRUCTION FOR EROSION, EXCESSIVE

AT LEAST FOUR TIMES A YEAR OR BEFORE IT EXCEEDS 0.5' IN DEPTH,

ACCUMULATION OF SEDIMENT AND TRASH. REPAIR ERODED SPOTS

THRIVING. CHECK FOR EROSION, INVASIVE TREE GROWTH, CLOGGING AND

TRASH, AND REMOVE ORGANIC MATTER, WEEDS, TRASH AND DEBRIS AS

NECESSARY. RE-SEED ERODED OR BARREN SPOTS IMMEDIATELY AFTER

DRY AND AT LEAST EVERY FIVE YEARS AFTER CONSTRUCTION.

INLET, OR WATER OF THE U.S. ")

SCHEDULE:

RAIN GARDEN

SEDIMENT CONTROL BARRIERS:

 THE PROPERTY LINES SHOWN HEREON, ARE COMPILED FROM PLANS AND DEED OF RECORD AND FIELD SURVEYS BY ATLANTIC DESIGN ENGINEERS, SEDIMENT CONTROL BARRIERS (SILT SOCK, ETC.) SHOULD BE INSPECTED MMEDIATELY AFTER EACH RUN-OFF PRODUCING RAINFALL EVENT AND AT

UTILITIES.

CONSTRUCTION NOTES:

NC. IN NOVEMBER AND DECEMBER OF 2018. THE HORIZONTAL DATUM IS THE NORTH AMERICAN DATUM OF 1983 (NAD83) MASSACHUSETTS STATE LANE, MAINLAND ZONE, BASED UPON A GPS SURVEY BY ATLANTIC

LEAST DAILY DURING PROLONGED RAINFALL. SEDIMENT DEPOSITS MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE—HALF THE HEIGHT OF THE BARRIER. SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURAL 2. EXISTING CONDITIONS DEPICTED HEREON ARE BASED UPON THE MASSACHUSETTS GEOGRAPHIC INFORMATION SYSTEM AND PARTIAL FIELD SURVEYS BY ATLANTIC DESIGN ENGINEERS, INC. IN NOVEMBER AND

- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS SHOWN AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES THAT MAY BE FOUND IN
- 4. CONTRACTOR SHALL VERIFY ALL CRITICAL ELEVATIONS AND INVERTS PRIOR TO CONSTRUCTION.
- WHERE AN EXISTING PUBLIC UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED AND THE INFORMATION FURNISHED TO THE UTILITY COMPANY AND OWNER FOR RESOLUTION OF THE CONFLICT
- 6. SUBSURFACE AND ENVIRONMENTAL CONDITIONS WERE NOT EXAMINED OR CONSIDERED AS PART OF THIS SURVEY. NO STATEMENT IS MADE CONCERNING THE EXISTENCE OF UNDERGROUND OR OVERHEAD CONTAINERS OR FACILITIES THAT MAY AFFECT THE USE OR DEVELOPMENT
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY DIGSAFE, THE TOWN OF NORTON HIGHWAY DEPARTMENT AND ALL UTILITY COMPANIES A MINIMUM OF 72 HOURS PRIOR TO CONSTRUCTION ACTIVITIES FOR LOCATION
- OF ALL UNDERGROUND UTILITIES AND UTILITY COMPANY APPROVALS. THE SAME BUSINESS DAY IN WHICH THE TRACK-OUT OCCURS OR BY THE END ALL BUILDINGS, SURFACE, AND SUBSURFACE IMPROVEMENTS ON AREAS ADJACENT TO THE SITE ARE NOT NECESSARILY SHOWN HEREON.
- THESE SURFACES, OR BY USING OTHER SIMILARLY EFFECTIVE MEANS OF SEDIMENT REMOVAL. YOU ARE PROHIBITED FROM HOSING OR SWEEPING TRACKED—OUT SEDIMENT INTO ANY STORMWATER CONVEYANCE, STORM DRAIN 9. THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVES. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL UTILITIES AND RIM AND INVERTS BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY

IND ALL DAMAGES THAT MIGHT OCCUR BY THE CONTRACTOR'S FAILURE

THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENTS OF ELECTRIC, TELEPHONE AND ANY OTHER PRIVATE UTILITIES WITH THE UTILITY COMPANY, IF NECESSARY. IF ANY INTERRUPTIONS IN SERVICE ARE NECESSARY TO ABUTTING PROPERTY AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURAL OR VEGETATIVE

TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND

- OWNERS, A MINIMUM OF 48 HOURS NOTICE SHALL BE GIVEN. 11. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL MEASURES IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AND MASSACHUSETTS HIGHWAY DEPARTMENT REQUIREMENTS FOR ALL WORK WITHIN PUBLIC STREETS.
- 12. AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATION SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
- 13. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL REQUIRED INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY COMPANIES ARE COMPLETED PRIOR TO INSTALLATION, BACKFILLING,
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL SURVEY CONTROL POINTS AND BENCHMARKS NECESSARY FOR THE PROPOSED

ANNOUNCED BUILDING POSSESSION, AND THE FINAL CONNECTION OF

- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ADEQUATE
- DISPOSAL OF ACCUMULATED SEDIMENT AND HYDROCARBONS TO BE IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL GUIDELINES AND RECULLATIONS RECORDS OF THE LOCATION AND ELEVATION OF ALL WORK INSTALLED. 16. THE CONTRACTOR SHALL INSTITUTE AND MAINTAIN ALL SAFETY MEASURES NECESSARY TO PROTECT THE PUBLIC DURING CONSTRUCTION, INCLUDING, BUT NOT LIMITED TO BARRICADES, SIGNS, FENCES, FLAGGERS, LIGHTING, POLICE DETAIL, AND ANY OPEN OVERNICHT.
 - TRENCHES ARE TO REMAIN OPEN OVERNIGHT. 17. THE CONTRACTOR SHALL KEEP THE PREMISES FREE FROM THE ACCUMULATION OF WASTE MATERIAL AND OTHER DEBRIS RESULTING FROM THE WORK. AT THE END OF CONSTRUCTION THE CONTRACTOR SHALL REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE. A THOROUGH INSPECTION OF THE WORK PERIMETER IS TO BE MADE
 - AND ALL DISCARDED MATERIALS, BLOWN OR WATER CARRIED DEBRIS, SHALL BE COLLECTED AND REMOVED FROM THE SITE. S. ALL WORK SHALL BE DONE IN STRICT COMPLIANCE WITH ALL APPROVED PERMITS AND WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES,
 - STANDARDS, ORDINANCES, RULES AND REGULATIONS. . CONTRACTOR TO DESIGNATE A SPECIFIC AREA FOR COMBUSTIBLE
 - 20. THE CONTRACTOR AND OWNER ARE RESPONSIBLE FOR COMPLIANCE WITH STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR CONSTRUCTION

- COLD PLANE AND OVERLAY

-PROPOSED 1-1/2" BIT.

1-1/2"


TOP COURSE

PROPOSED 2" BIT. BINDER COURSE


PROPOSED 8"-


GRAVEL SUBBASE


M 1.03 TYPE B



CURB SET AT ELEVATION







4' WIDE BERM

SEE RIP-RAP

APRON DETAIL

4" CPP OUTLET

SEEDED SLOPES, BERM

30-40% COMPOSTED LEAVES

NOTE: SEE PLANS FOR

OVERFLOW LOCATION(S)

ELEV=65.50

AND BOTTOM


SOIL FILTER MIX:


40% CLEAN SAND

20-30% TOPSOIL

MAX. SIDESLOPES (TYP)

APRON







SAWCUT AT LIMIT OF RECONSTRUCTION (TYP.)


DETECTABLE WARNING PANELS ON WHEELCHAIR RAMPS FOR

ONE CONTINUOUS DIRECTION OF PEDESTRIAN TRAVEL

(NOT TO SCALE)









P.O. Box 1051, Sandwich, MA 02563